

SAFE WORK METHOD STATEMENT (SWMS)

DOCUMENT CONTROL	
SWMS_ID	SWMS-012
SWMS_Title	Replace Filters in New York Blower Baghouse
SWMS_Version	1.1
SWMS_Type	☐ Core SWMS ☒ Routine Task SWMS ☐ Non-Routine Task SWMS
Status	☐ Draft ☐ Current ☐ Superseded
Authorised_By	Chris Foster
Authorised_Date	26/06/2026
Review_Date	25/07/2027
Review_Period_Months	12
Review_Trigger	☒ Initial Issue ☐ Incident ☐ Legislative Change ☐ Procedure Change ☐ Equipment Change ☐ Risk Assessment Review ☐ Scheduled Review

REVISION HISTORY

Version	Date	Change Summary	Authorised By
1.0	12/07/2025	Initial Issue	Chris Foster
1.1	26/06/2026	Scheduled Review	Chris Foster

SWMS ID: SWMS-012	SWMS Title: Replace Filters in New York Blower Baghouse	
Prepared By: Chris Foster		Date: 24/06/2026
Business Name: Tuan Biomass Albioma		
Description of Task: Replace bag house filters		
Reason for analysis: ☐ New task/plant ☒ High Risk Task ☐ Change ☐ Regular review ☐ Post-Incident ☐ Contractor (to complete) Task ☒ Non-Routine Task ☐ Maintenance/Repair ☐ Other (specify):		
SWMS Team Names: 1. Chris Foster	2. David Knight	3.
4.	5.	6.
Permits Required: (circle) Confined Space ☒ Isolation ☒ Hot Work ☐ PPE Requirements:                 		
Other:		

SAFE WORK METHOD STATEMENT (SWMS)

Potential Environment Hazards	Fire/Emergency Response Equipment
☒ Noise / vibration ☒ Air pollution – dust / smoke / fume ☒ Spills to ground ☒ Spills to water / drains / waterways ☐ Soil erosion / contamination ☐ Hazards to flora & fauna ☒ Waste generation & disposal ☒ Hazardous chemicals / substances ☐ Vegetation / bushfire risk ☐ Other: _____	☒ Fire extinguisher — Location: Main shed wall ☒ Fire hose / hydrant — Location: Walking Floor, Shavings silo, inside shed ☒ First aid kit — Location: Smoko Room ☒ Spill kit — Location: Inside the North Entry door ☒ Emergency eyewash / shower — Location: Outside the workshop ☒ Emergency assembly point — Location: ☒ Communication method: ☐ Radio ☐ Phone ☐ Verbal ☒ Emergency contact No: 0439 013 224
Hazards Identified	
☒ Electricity ☒ Confined Space ☒ Stored Energy ☒ Extreme Temperatures ☒ Dust and or fume ☒ Hazardous Manual Tasks ☒ Psychological ☒ Traffic/Mobile Plant ☒ Ignition Sources ☒ Lighting ☒ Machinery & Equipment ☒ Person/Object Falling ☐ Pressure (air, water, gas) ☐ Object Falling ☐ Hazardous Chemicals ☐ Hot Work ☐ Other workers/people	
Other Comments:	

REQUIRED CORE SWMS

List the Core SWMS that also apply to this task. Linked Core SWMS must be read and signed on through the online SWMS Register together with this SWMS.

Applies	Core SWMS	Linked SWMS_ID
☒	Isolation and LOTO	SWMS-026
☐	Hot Work	SWMS-005
☒	Confined Space Entry	SWMS-024
☒	Working at Heights	SWMS-025
☐	Crane and Lifting Operations	SWMS-026
☐	Working on Un-isolated plant	SWMS-027

CRITICAL CONTROLS

The following critical controls must be in place and verified before work starts.

#	Critical Control (must be in place before work starts)
1	Complete isolation and verify zero energy before opening the baghouse.
2	Use approved access equipment and fall protection where there is a risk of falling.
3	Wear required PPE, including P2 respirator, eye protection and gloves, to control dust exposure.
4	Use safe manual handling techniques or mechanical assistance when removing and installing filters.
5	Maintain good housekeeping and control dust to prevent slips and combustible dust hazards.
6	Inspect the work area, secure all access doors and complete a controlled restart before returning the plant to service.

If a critical control cannot be implemented, work must stop and the SWMS must be reviewed before proceeding.

CONTROLLED MASTER DOCUMENT

Doc Id: SWMS – 001- 2024-v2.0	Page 2 of 4
Doc Owner: Tuan Safety and Compliance Manager	Issue Date: 20 November-2024
Last Review: 24-Jun-2026	Version No: 001

SAFE WORK METHOD STATEMENT (SWMS)

Key Steps in Logical Order		Hazards/Risks to Workers or Public	Risk Score	Control Measures	Residual Risk Score
1	Complete the telehandler pre-start inspection, obtain required permits and isolate the surge bin screws, pulse cleaning air system and all other required energy sources. Verify zero energy before commencing work.	Unexpected plant start-up, stored energy, electrical hazards, mobile plant interaction.	High	Complete Isolation Request, apply personal locks and tags, verify zero energy, complete telehandler pre-start inspection, establish exclusion zone and confirm permits are in place.	Low
2	Start the New York blower at 10–20% and confirm adequate ventilation of the baghouse and surge bin throughout the task.	Dust inhalation, poor air quality, oxygen deficiency, heat stress.	High	Operate blower for continuous ventilation, wear P2 respirators, continuously monitor atmosphere and stop work if conditions become unsafe.	Low
3	Access the baghouse platform using the fixed access and open the top inspection doors to gain access to the filter bags.	Falls from height, dropped objects, slips and trips.	High	Use fixed platforms with handrails, maintain three points of contact, secure tools, barricade area below and wear required PPE.	Low
4	Remove the pulse cleaning pipes and snap bands to release the filter bags.	Pinch points, manual handling injuries, dropped components.	Med	Use correct tools, wear gloves, maintain stable footing and use team lifting where required.	Low
5	Push the used filter bags down through the tube sheet into the surge bin.	Dust exposure, falling filter bags, overreaching.	Med	Push filters in a controlled manner, keep workers clear below, wear respiratory and eye protection and maintain communication.	Low
6	Workers inside the surge bin manually remove the filter bags and pass them through the inspection access opening to the worker outside.	Confined space hazards, manual handling, awkward postures, dust exposure.	High	Confined Space Entry Permit, standby person, continuous atmospheric monitoring, mechanical ventilation, effective communication and safe manual handling techniques.	Low
7	The worker outside places the removed filter bags onto the telehandler forks positioned as close as practicable to the top of the surge bin.	Falling objects, crush injuries, telehandler movement.	Med	Position telehandler on stable ground, maintain exclusion zone, communicate with operator and stack filters securely.	Low
8	Load new filter bags onto the telehandler forks, lift to the surge bin platform and pass the filters to the worker on top of the baghouse.	Manual handling, dropped loads, falls from height.	High	Lift using telehandler, pass filters in a controlled manner, maintain secure footing, avoid overreaching and communicate throughout the lift.	Low
9	Install the new filter bags, refit the snap bands and reinstall the pulse cleaning pipes.	Pinch points, repetitive strain, incorrect installation.	Med	Install filters correctly, secure snap bands and pulse cleaning pipes, inspect installation before progressing.	Low

CONTROLLED MASTER DOCUMENT

Doc Id: SWMS – 001- 2024-v2.0	Page 3 of 4
Doc Owner: Tuan Safety and Compliance Manager	Issue Date: 20 November-2024
Last Review: 24-Jun-2026	Version No: 001

SAFE WORK METHOD STATEMENT (SWMS)

10	Inspect all filter bags, snap bands and pulse cleaning pipes to confirm they are correctly installed. Remove all tools, equipment and waste from the work area.	Forgotten tools, poor housekeeping, trip hazards.	Med	Complete final inspection, remove waste and tools, account for all equipment before closing access doors.	Low
11	Close and secure all inspection doors, remove isolations, complete a controlled restart and monitor the baghouse to confirm normal operation.	Unexpected start-up, equipment failure, airborne dust release.	Med	Remove personal locks in accordance with the LOTO procedure, notify affected personnel, complete a controlled restart and monitor the plant for abnormal operation or air leaks.	Low

Add additional job steps, hazards and controls as required

All relevant workers must be consulted during the development and review of this SWMS and made aware of the control measures and all required permits. Worker consultation and sign-on are recorded through the online SWMS Register.

ONLINE SWMS MANAGEMENT

Worker sign-on is completed through the online SWMS Register.

Workers are required to read and sign onto this SWMS once per review period, or sooner if the SWMS is revised, superseded, or changed due to an incident, equipment change, procedure change, legislative change, or risk assessment review.

Before each task commences, the team or person in control of the work must review the SWMS through the online task review system and confirm whether anything has changed from the approved SWMS.

If no changes are identified, the task may proceed once all workers are confirmed as current against the required SWMS.

If changes are identified, the changes and additional controls must be recorded in the online Task Record before work proceeds.

Supervisor review is required where the change affects the work method, plant, equipment, location, hazards, permit requirements, or critical controls.

System of record

This Word document is the controlled master SWMS. The PDF is the worker-view copy. The HTML tablet page is used to view the SWMS and complete the task review.

Worker sign-off is stored in Worker_SWMS_Register. Daily task reviews are stored in Task_Records. Review dates and version status are controlled in SWMS_Library.

AUTHORISATION		
Approved by: Chris Foster	Position: Safety and Compliance Manager	Approval Date: 25/06/2026

CONTROLLED MASTER DOCUMENT

Doc Id: SWMS – 001- 2024-v2.0	Page 4 of 4
Doc Owner: Tuan Safety and Compliance Manager	Issue Date: 20 November-2024
Last Review: 24-Jun-2026	Version No: 001